



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963
10-14-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ray Richardson of Southwest Casing Pulling has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Hudson Petroleum Inc.

Complete Address: Box 333, 4720 Rainbow, Kansas City, Kansas

Lease Name: Westafer Well No. # 1

Location: NE/4 Sec. 17 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3505 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Richardson was instructed to plug the well as follows:

- 273' of 8 5/8" surface pipe, cemented with 225 sacks.
- 3496' of 5 1/2" long string, cemented with 100 sacks. Sand
- to 3475', cement with 5 sacks. Fill hole with mud to 250',
- 10' rock bridge, cement with 20 sacks. Fill hole with mud
- to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent