



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Brown of Gabbert & Jones Inc. has this date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co.

Complete Address: 217 N. Water Wichita, Ks

Lease Name: Ruth DeWerff Well No. 3-D

Location: SE/NW/SW Sec. 9 Twp. 21s Rge. 12 (E)(W) W

County: Stafford Total Depth 3491 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

444 ft 8 5/8 surface pipe cemented with 325 sacks. Pump
30 sacks cement to 650 ft. 2nd plug at 400 ft with 20 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co. Great Bend, Ks

Very truly yours,

J. Russell B. Boster
Conservation Division Agent