

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.185.3022.1.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ACST. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Vaughn Francis of Terrel Drilling & Prod. has this date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company

Complete Address: 816 Bitting Bldg., Wichita, Kansas

Lease Name: Wright Well No. # 1

Location: SW NE NE Sec. 14 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3720 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

318' of 8 5/8" surface pipe, cemented with 250 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent