

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212. North Market
Wichita 2, Kansas

Operator's Full Name Virginia Drilling Company, Inc.

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name Burhenn Well No. # 1

Location SW NW NE Sec. 9 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Virginia Drilling Company, Inc.

Address: 712 Brown Bldg., Wivhita, Kansas License No. _____

Operation Completed: Hour 2:30 PM Day 25th Month April Year 1965

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 135'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 240', and cemented with 25 sacks, through the
drill pipe. Fluid level in the hole was now at 34'. 2nd cementing
plug was bridged solid with dry cement and hulls on fluid at 34', and
cemented with 8 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 4/26/65

INV. NO. 1044-W

Signed: Archie Elving
Well Plugging Supervisor