



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date October 30, 1958, authorized the following plugging operation:

Operator's Full Name: Tomlinson & Kathol

Complete Address: 216 East Waterman, Wichita, Kans.

Lease Name: Kasselmann Well No. 1

Location: SW NE NE Sec. 5 Twp. 21 Rge. 12 (E) (W) X

County: Stafford Total Depth: 3480

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

256' of 8 5/8" surface casing circulated with cement. Fill hole to 250' with heavy drilling mud. Place cementing plug at 250'. Place 20 sack cement through drill pipe. Heavy drilling mud to 40'. Place cementing plug and 10 sack cement from 40' to base of cellar.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED COMMISSION

107 1958 CONSERVATION DIVISION WICHITA

11-7-58