

15.185.00206.0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

NOV 4 1966
CONSERVATION DIVISION
Wichita, Kansas
11-4-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shallow Water Refining Company

Complete Address: 1325 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Tindall "A" Well No. # 1

Location NE SE NW Sec. 13 Twp. 21 Rge. 12 (E) (W) W

County Stafford County Total Depth 3546'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:30PM Day 3rd Month Nov. Year 1966

The Above well was plugged as follows:

242' of 8 5/8" surface pipe, cement circulated. 3542' of 5 1/2" long
string, cemented with 200 sacks. Plug back T. D. 3492'. Top perferation
3432'. Bottom of the hole was sanded to 3400', and cemented with 5 sacks,
through the dump bailer. 1680' of 5 1/2" long string was recovered from
the hole. 10 sacks of Gel-Mud was pumped in the 5 1/2" casing at 400',
and 25 sacks of cement was pumped in to the 5 1/2" casing at 240'. Fluid
in the hole was bailed down to 40', bridge plug and rock bridge from
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elwing
Well Plugging Supervisor

DATE 11/4/66
INV. NO. 4230-11