

15-009-03349-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name M. J. Bove  
Complete Address: 754 E. Wichita, Russell, Kansas  
Lease Name Reiman Well No. # 4  
Location NW SW SW Sec. 23 Twp. 16 Rge. 12 (E) (W) W  
County Barton Total Depth 3366  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Barnes & Sons Pipe Pulling Company  
Address: 1450 Maple, Russell, Kansas License No. # 9  
Operation Completed: Hour 5 P.M Day 22 Month 8 Year 1964

The Above well was plugged as follows:

8 5/8" 158' Cwc.

Set bottom plug @ 3100' & dumped 5 sax cement with dump bailer. Pulled pipe to 450'; circulated hole with mud; displaced 25 sax cement thru pipe @ 300'. Pulled pipe to 155'; displaced 20 sax cement with Sun Cementing Company's pump truck. Pulled remaining pipe; set rock bridge & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 8/26/64  
INV. NO. 9715-W

Signed: Don Truman  
Well Plugging Supervisor