

15-009-03351-00-00

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 99-23 Location: SW SW SW

County: Barton Sec. 23 Twp. 16 Rge. 12W (E) (W)

Name of Field or Pool: \_\_\_\_\_ Total Depth: 3328

I have this date completed supervision of plugging of:

Well No. # 7 Lease Reiman

Operator's Full Name M. J. Bone & BOVE

Complete Address: 754 E. Wichita Avenue, Russell, Kansas

Plugging Contractor: Arnett Casing Pulling Co.

Address: 172 W. 3rd., Hoisington, Kansas License No. 265

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour \_\_\_\_\_ Day 19 Month May Year 1958

The above well was plugged as follows:

Sand back to 3350' & 5 sax cement with dump bailer. Shot pipe  
off, pulled same. Pumped 15 Bbl. mud in hole @ 300' & 25 sax cement  
with pump truck. Mud to 40', rock bridge, & 10 sax cement to the base  
of the cellar.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: Dow Truman  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

MAY 22 1958  
5-22-58  
CONSERVATION DIVISION  
Wichita, Kansas

Reviewed: J. Lewis Brock  
Field Supervisor

Signed: \_\_\_\_\_  
Well-Plugging Supervisor

Remarks:

PLUGGING  
FILE SEC. 23 16 R. 12W  
BOOK PAGE 99 LINE 23

15-009-03351-00-00  
 WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 508 E. Murdock Wichita, Kansas

COPY

Company - W. L. HARTMAN  
 Farm - Riemann No. 7

SEC. 23 T. 16 R. 12W  
 SW SW SW

Total Depth. 3385 $\frac{1}{2}$   
 Comm. 4-4-50 Comp. 4-18-50  
 Shot or Treated.  
 Contractor. H & H Drilg. Co.  
 Issued. 6-24-50

County. Barton  
 KANSAS


CASING:  
 8 5/8" 165' cem. w/120 sx  
 5 1/2" 3356' cem.w/ 125 sx

Elevation. \_\_\_\_\_  
 Production. Pot. 56 bbls. per 19  
 hour test

Figures Indicate Bottom of Formations.

cement	165
shale & sand	410
sand	470
shale, sand & shells	780
redbed	799
Anhydrite	830
sand & shale	1112
shale	1599
shale & lime	1890
limo	2028
limo & shale	2458
shale	2675
limo & shale	2896
limo	2969
limo & shale	3110
limo, RTD	3360
limo	3367
limo & shale	3369
limo	3384
sandy limo	3385 $\frac{1}{2}$
Total depth	

Tops: (Derrick Floor Data)

Topoka	2674
Hoobnor	2995
Douglas?	3031
Lansing-KC	3086
Sooy Sand?	3353 $\frac{1}{2}$ Corr.
Arbucklo	3356 $\frac{3}{4}$ Corr.
Total Depth (RTD)	3359 $\frac{1}{2}$ Corr.
Total depth	3383

Remarks:  
 Jotted shale pits at 2810;  
 Trip @ 2907 SIM -Ok  
 Circ. 1 hr. @ 3109  
 Now bit @ 3133; S.R. 3135-36; Circ.  
 1 hr. 3142  
 Circ. 1 hr & 20 mins. @ 3157; Circ.  
 3210 & 3241; Circ. @ 3333, 3355, 3360'  
 Drill Stem Test #1 3097-3133,  
 open 50 mins. Light blow 22 mins.  
 rec. 30' sli salty mud with few  
 small spots free oil on top 10  
 min. BHP O#  
 Drill Stem Test #2 3132-3142,  
 open 30 mins. rec. 5' mud, no  
 shows, 10 min, BHP O#  
 Drill Stem test #3 3190-3210,  
 open 30 mins. sli blow 5 mins.  
 rec. 5' mud, no show, 5 mins.  
 BHP O#  
 Drill Stem Test #4 3231-3241,  
 open 30 mins. light blow 3 mins.  
 rec. 5' mud, no show, 5 mins.  
 BHP O#

**RECEIVED**  
 STATE CORPORATE COMMISSION  
 JUN 4 1958  
 CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC. 23 T. 16 R. 12W  
 BOOK PAGE 99 LINE 23