

15-009-03352-00-00

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 53-29

LOCATION 7 1/2 - NW - NW

SEC 23 TWP. 16 RGE. 12 W

Dry Hole          Abandoned Oil Well  Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 1 Lease Riemann

Operator Great Bend Pipe & Supply Address Box 414 Great Bend Kans.

Field          County Barton

Total Depth 3464 Feet.

Plugging Contractor Horner Casing Pulling Co

Plugging Contractor's License No. 49

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 708' C.W.C. Oil string 4 1/2" O.D.  
@ 3461 w/ 300 st Cem. Sanded hole to 3450'  
and dumped 3 st Cem. Shot off and pulled  
4 1/2" casing mudded hole to 275' set rock bridge  
and run 20 st Cem. Mud to 35' rock bridge  
and 10 st Cem to base of cellar

STATE CORPORATION COMMISSION

AUG 11 1954

Warren H. Horner  
District Conservation Agent

CONSERVATION DIVISION  
Wichita, Kansas

Date Aug 9, 1954

**PLUGGING**  
FILE SEC 23 T 16 R 12W  
BOOK PAGE 53 LINE 29