

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 56-18

LOCATION NE-SW-NW

SEC. 23 TWP. 16 RGE. 12w

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Reimann "B"

Operator Bennett & Robert Oil Operators Address Russell Kans.

Field _____ County Barton

Total Depth 3394.5 Feet.

Plugging Contractor Miller Casing Pulling Co.

Plugging Contractor's License No. 12

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/4" @ 293' c.w.c. Oil string 5 1/2"
@ 3399.5 w/ 75 st Cem. Crushed rock to
3380' and dump 5 st Cem. Shut off and
pulled 5 1/2" casing. Mudded hole to
290' set rock bridge and run 20 st
Cem. mud to 35' rock bridge and 10
st Cem to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1954
8-18-54

CONSERVATION DIVISION
Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date Aug 16, 1954

PLUGGING
FILE SEC 23 T 16 R 12W
BOOK PAGE 56 LINE 18