

15.185.30261.0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 - 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name Westafer Well No. # 1

Location SW NW SE Sec. 17 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drilling Company, Inc.

Address: 500 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 6:30AM Day 3rd Month May Year 1966

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid
level in the hole was at 120'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug
bridged solid with 1/2 sack of hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/5/66
INV. NO. 3169-W

Signed: Aubie Elving
Well Plugging Supervisor