

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 127-19

LOCATION NE. 12E. 7W

SEC. 17 TWP. 21 RGE. 12-45

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Johnson

Operator Norby Drilling Co Address 352 N. Broadway - Wichita - Kansas

Field \_\_\_\_\_ County Stafford

Total Depth 3545 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8 - 252 ft. Circulated with cement  
5 1/2" casing set at 3490 ft. & cemented. Plugged  
back with sand to 3350 ft. Dumped 5 sacks of cement  
at 3350 ft. Shot off & hulled the 5 1/2" casing - mud  
& 152 ft. Set 4 inch bridge x 15 sacks of cement  
at 242 ft. mud to 35 ft. Bridge x 40 sacks  
of cement at the surface  
The West Supply Co. Plugging Contractors

FILE  
STATE C.

1-30-52

C. H. Stouck  
District Conservation Agent

Date 1-28-52

FILE SEC-17 TWP-21 RGE-12-45  
BOOK PAGE 127 LINE 19