

15.185.19490.0000

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1963
10-14-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Hudson Petroleum Inc.

Complete Address: Box 333, 4720 Rainbow, Kansas City, Kansas

Lease Name Westafer Well No. # 1

Location NE/4 Sec. 17 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3505

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:00AM Day 11th Month Oct. Year 1963

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cemented with 225 sacks. 3496' of 5 1/2" long
string, cemented with 100 sacks. Bottom of hole was sanded to 3475', and
cemented with 5 sacks. Fluid was moving in the hole and a squeeze job was
decided. 10 sacks of Gel-Mud and 75 sacks cement was pumped into surface
pipe, through an 8 5/8" swage, to a pressure of 250 lbs.

This cementing job was done by Sun Cementing Co.

2972' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/14/63

INV. NO. 7885-W