


KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Well Plugging Authority,
 issued January 25, 1968.

RECEIVED
 STATE CORPORATION COMMISSION
FEB 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Walter J. Nelson

Complete Address: 2072 Marc, Salina, Kansas 67401

Lease Name Roberts Well No. # B-1

Location C NW SW Sec. 14 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3831'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:00AM Day 9th Month February Year 1968

The Above well was plugged as follows:

268' of 8 5/8" surface pipe, cemented with 185 sacks. 3830' of 5 1/2" long string,
cemented with 160 sacks. Plug back T.D. 3820'. Top perferation 3309'. Bottom of
the hole was sanded to 3275', and cemented with 5 sacks, through the dump bailer,
with cement from 3275' to 3235'. 2584' of 5 1/2" long string was recovered from the
hole. Bridge plug was pushed in fluid to 260', bridge plug and rock bridge from
260' to 250'. 4 sacks of cement was mixed in a barrel, and put on plug at 250',
through the dump bailer, and let set over-night. Next day hole was bailed dry,
and 21 sacks of cement was added to the plug, with cement from 250' to 175'. Hole
was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10
sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aulie Elving
 Well Plugging Supervisor

DATE 2/13/68

INV. NO. 7252-W