

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 7 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name S. A. Murphy

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name Grow "B" Well No. # 1

Location C s/2 NW NW Sec. 14 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3567'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 1:30 PM Day 30th Month August Year 1965

The Above well was plugged as follows:

285' of 8 5/8" surface pipe, cemented with 150 sacks. 3531' of 4 1/2"
long string, cemented with 50 sacks. Top perferation 3362'. Plug was
pushed to 3300', 10' of rock bridge, and cemented with 3 sacks. 3109'
of 4 1/2" long string was recovered from the hole. Hole was bailed down
to 200', rock bridge from 200' to 190', and cemented with 25 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/1/65
INV. NO. 1930-4