

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County, Sec. 14 Twp. 21 Rge. 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE SE  
Lease Owner Petroleum, Inc.  
Lease Name Schartz Well No. 1  
Office Address 100 Derby Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 8, 19 51  
Application for plugging filed February 8, 19 51  
Application for plugging approved February 10, 19 51  
Plugging commenced February 8, 19 51  
Plugging completed February 8, 19 51  
Reason for abandonment of well or producing formation Dry Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3742 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 240'. Cemented and dis-  
placed through drill pipe 15 sax. Filled  
hole with heavy mud to 30'. Placed wooden  
plug at 30'. Filled hole to surface with  
10 sax cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 21 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.  
Address 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Eric H. Jager (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager  
100 Derby Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 51

Charlotte Heidman  
Notary Public.

My commission expires October 13, 1954

PLUGGING  
FILE SEC 14T21 R14W  
BOOK PAGE 66 LINE 1

WELL LOG SCHATZ #1

Petroleum, Inc., Lease Owner

Section 14, Twp. 21S, Rge. 14W

Garvey Oil, Contractor

Location: NE SE SE

Rotary Total Depth: 3742'

County: Stafford, Kansas

Commenced: January 28, 1951

Production: D & A

Completed: February 8, 1951

Elevation: 1927 D.F.

Casing: 243' of 8 5/8"

Figures below indicate bottom of formation:

			Tops
25	Surface Soil		
191	Sand		
243	Shale & Shells	3250	Heebner
580	Shale & Red Bed	3272	Toronto
818	Red Bed	3369	Brown Lime
840	Anhydrite	3379	Lansing
1295	Shale & Shells	3596	B.K.C.
1780	Lime & Shale	3629	Viola
1945	Lime	3675	Simpson
2095	Lime & Shale	3717	Arbuckle
2555	Shale & Shells		
2755	Shale		
2895	Lime & Shale		
2965	Lime		
3100	Lime & Shale		
3170	Lime		
3380	Lime & Shale		
3420	Lime		
3709	Shale		
3742	Lime		
3742	R.T.D.		

3717 - 3379 = 3378  
 1927 - 1927 = 0  
 1927 - 1452 = 475

D & A

I hereby certify that this is a true and correct log of the above mentioned well.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 FEB 21 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

PETROLEUM, INC.  
*Eric H. Jager*  
 Eric H. Jager

STATE OF KANSAS: :  
: : SS.  
SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 13th day of February, 1951.

My commission expires: 10-13-54

*Charlotte Heidman*  
Notary Public

**PLUGGING**  
 FILE SEC 14 T 21 R 14 W 2  
 BOOK PAGE 66 LINE 1