


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 14 Twp. 21 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SW 1/4 SW 1/4 SW 1/4
Lease Owner Durbin Bond & Co., Inc. and Lewis Drilling Company
Lease Name Rychlec Well No. 1
Office Address 915 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-21 19 56
Application for plugging filed 7-21 19 56
Application for plugging approved 7-21 19 56
Plugging commenced 7-25 19 56
Plugging completed 7-25 19 56
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Depth to top Bottom Total Depth of Well 3790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	860'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240'. Set bottom plug with 1/3 sack hulls & 20 sacks cement thru drill pipe. Set top plug at 20' with 1/3 sack hulls and 10 sacks cement to top of pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. Fred Hambright (employee of owner or (owner) operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 56

My commission expires August 20, 1956

Arthur R. Derrington
(Arthur R. Derrington) Notary Public.

FILED
COMMISSION
8-2-56
DIVISION

PLUGGING
FILE SEC 14 T 21 R 14w
BOOK PAGE 84 LINE 22


15.185.00939.0000

WELL LOG

COMPANY Durbin Bond & Co., Inc. and Lewis Drilling Co. SEC. 14 T. 21S R. 14W
FARM Rychlec NO. 1 LOC. SW $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$

TOTAL DEPTH 3790'
COMM. 7-15-56 COMP. 7-25-56
SHOT OR TREATED
CONTRACTOR Lewis Drilling Company
ISSUED

COUNTY Stafford
KANSAS



CASING
20 10
15 8 5/8" - 860'
12 6
13 5

ELEVATION 1932 RB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 185	Sand & Gravel
185 - 380	Shale & Shells
380 - 845	Red beds
845 - 870	Anhydrite
870 - 925	Red beds
925 - 3510	Lime & shale
3510 - 3560	Lime
3560 - 3679	Lime & shale
3679 - 3690	Chert & Conglomerate
3690 - 3790	Lime
3790 - T. D.	

Geologic Tops:

Anhydrite	845'
Heebner	3278'
Toronto	3299'
Douglas	3319'
Iaton	3397'
Lansing	3408'
Base Kansas City	3640'
Cherty Conglomerate	3678'
Cherty Viola	3688'
Simpson Shale	3725'
Arbuckle	3755'

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 14 T. 21 R. 14W
BOOK PAGE 84 LINE 22

State of KANSAS }
County of SEDGWICK } ss:

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Rychlec #1 well.

Subscribed and sworn to before me this 31st day of July 19 56

My Commission Expires: August 20, 1956

Arthur R. Derrington
NOTARY PUBLIC
(Arthur R. Derrington)