

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County. Sec. 14 Twp. 21 Rge. (E) 14 (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE NE NW  
Lease Owner Chas. Hulme Drilling Contractor  
Lease Name Curtis Well No. 1  
Office Address P.O. Box 36, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 25, 19 53  
Application for plugging filed March 25, 19 53  
Application for plugging approved March 25, 19 53  
Plugging commenced 8 A.M. March 25, 19 53  
Plugging completed 10 A.M. March 25, 19 53  
Reason for abandonment of well or producing formation Dry Hole

NORTH

Section Plat grid with 'X' in the top-left cell.

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 3760 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

To sack cement from 300 feet to 240 feet;  
10 sacks cement from 35 feet to ground level.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C. E. Byars  
Address P.O. Box 36, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
C. E. Byars (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Byars  
P.O. Box 36, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 19 53  
Notary Public.

My commission expires October 15, 1953

PLUGGING  
FILE SEC 14 T 21 R 14 W  
BOOK PAGE 87 LINE 35

## DRILLER'S LOG

Well: Curtis #1, NE NE NW 14-21-14W, Stafford County, Kansas  
 Operator: Chas. Hulme Drilling Contractor  
 Date Well Commenced: March 13, 1953  
 Date Well Completed: March 25, 1953  
 Casing Record: 310 Ft. 8 5/8" surface pipe cemented with 200 sacks cement.

Shale and Clay	0	310
Sand	310	370
Red Bed and Shells	370	790
Anhydrite	790	825
Shale and Shells	825	1310
Shale and Lime	1310	1630
Lime	1630	2000
Lime and Shale	2000	2080
Lime	2080	2185
Shale	2185	2285
Shale and Shells	2285	2410
Shale and Lime	2410	2535
Shale	2535	2675
Shale and Lime	2675	2795
Shale and Shells	2795	2949
Lime	2949	3299
Lime and Shale	3299	3363
Lime	3363	3666
Chert and Lime	3666	3681
Shale and Lime	3681	3760
TD	3760	

State of Kansas, County of Barton, ss.

C. E. Byars, General Manager of the Chas. Hulme Drilling Company, who drilled the above - described well, first duly sworn on oath says: That I have knowledge of the facts, statements, and matters herein contained and that to the best of my knowledge the same are true and correct. So help me God.

*C. E. Byars*

P.O. Box 36, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 25 day of March, 1953

*Ray Richardson*  
 Notary Public

My commission expires October 15, 1953.

MAR 27 1953  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

**PLUGGING**  
 FILE SEC 14-T-21-14W  
 BOOK PAGE 87 LINE 35