

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 14 TWP. 21 RGE. 14 #W' (14)
Location as in quarters or footage from lines:
NE SE SW

Lease Owner L. D. Davis
 Lease Name Rychlec B Well No. 1
 Office Address Route 1, Box 183-B, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed May, 1979
 Application for plugging filed 03-12-85
 Plugging commenced 03-15-85
 Plugging completed 03-22-85
 Reason for abandonment of well or producing formation non commercial
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation Lansing Kansas Depth to top 3466 bottom 4301 T.D. 3790
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	307	8 5/8"	307	0
	Production	0	3789	4 1/2"	3789	2498'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3416', 4 sacks on top. shot casing at 3000'.
 Pipe would not come, shot at 2500'. Pulled pipe. 03-15-85

03-22-85 : Halliburton pumped 2 sacks of hulls, 10 sacks of Gel,
 50 sacks cement and 10 sacks gel, 1 1/2 sacks hulls, put in wiper
 plug, 8 5/8", 100 sacks of cement. Max pressure 300, shut in
 pressure 250#. Plug down 12:15 03-22-85.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 02 1985
 4-2-85
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor D S & W WELL SERVICING, INC. Operator No. 6901

STATE OF Kansas COUNTY OF Barton, ss.
Robert Strube (employee of owner) or (owner) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.
 (Signature) Robert L. Strube
Clafin, Ks.
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1985

NOTARY PUBLIC - State of Kansas
 BESSIE M. DeWERFF
 My Appt. Exp. May 29, 1985

Bessie M. DeWerriff
 Bessie M. DeWerriff Notary Public.

NOTARY PUBLIC - State of Kansas
 BESSIE M. DeWERFF
 My Appt. Exp. May 29, 1985

My Commission expires _____

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

ICER ARDIS - OPERATOR

RYCHLEC B - 1
NE SE SW 14-21-14S
STAFFORD COUNTY, KANS.

T. D. 3970
ELEV. 1934 KB

COMMENCED: 12-5-78
COMPLETED: 12-11-78

CASING

CEMENT

3-5/8" set at 307'
4-1/2" set to 3739' (1' off bottom)

4/250 sx 50/50 Pozmix, 20 gal 3%CC
4/125 sx 30/40 Pozmix, 17 gal salt
2/ 3/4 of 15 SFH2, 20 bbl. salt flush

FORMATION

DEPTH

Clay & sand	0 - 169
Shale	169 - 653
Shale & red bed	653 - 835
Anhy	835 - 857
Shale & Shells	857 - 2281
Shale w/Lime	2281 - 2573
Lime & Shale	2573 - 2947
Lime	2947 - 3163
Shale & Lime	3163 - 3284
Lime & Shale Streaks	3284 - 3294
Lime	3294 - 3790

TOPS

Heebner	3270
Wagon	3170
Douglas	3311
Brn. Lime	3391
Lansing	3401
B. K/C	3607
Cong.	3632
Viola	3650
S. Sh.	3700
Arb.	3745
T.T.P.	3790

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1985

CONSERVATION DIVISION
Wichita, Kansas

APPROVAL

State of Kansas County of Barton

I, Larry Curtis of the L. D. DRILLING COMPANY

being first sworn on oath, State: That I have knowledge of the facts
~~contained in this log and that the same are true and correct.~~

Larry Curtis
Larry Curtis

Subscribed and sworn to before me this 11th day of December 1978.

My commission expires: 5-20-81

Bessie M. Dewerff
Notary Public; Bessie M. Dewerff

BESSIE M. DEWERFF
ST/ NOTARY PUBLI
BARTON COUNTY, KANSAS
EXP. 5-20-81

JOB LOG

WELL NO. 10-1 LEASE WY-11000 TICKET NO. 27216

CUSTOMER L. D. DILLON, JR. PAGE NO. 1

JOB TYPE 1" JOE TO 12" JOE DATE 12/1/77

FORM 2013 R-2 15-185-20871-0000

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1200							1500 8' JOE
	1215							START 1" JOE
	1245							1" JOE TRACK - 12" JOE TRACK IN OPERATIONAL
								TRUCK UP TO 12" JOE
								1" JOE TRACK - 12" JOE TRACK IN OPERATIONAL
1170	6		20000			500		TAKE PUMPING 12" JOE TRACK. FLOWING 12" JOE TRACK. 10" JOE TRACK. FLOWING WITH 50% GEL. 10" JOE TRACK WITH 50% GEL. 10" JOE TRACK WITH 50% GEL. 10" JOE TRACK WITH 50% GEL. 10" JOE TRACK WITH 50% GEL.
1215						250		THROUGH MIXING 12" JOE TRACK. FLOWING 12" JOE TRACK.

APR 0