

WELL PLUGGING RECORD

Give All Information Completely  
Make Required "Seal" or  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 14 Twp. 21N Rge. 11 (11) (W)

Location as "NE/CNW/SW" or footage from lines NE/NE/NE

Lease Owner Mr. J.W. Bird

Lease Name Wright 28 Kennedy Street, Bradford, Pennsylvania

Office Address ~~of Mr. J.W. Bird, 1408 Mile High Center, Denver, Co.~~

Character of Well (completed as Oil, Gas or Dry Hole) Oil ~~Concrete~~

Date well completed 12/26/50 19

Application for plugging filed Yes 19

Application for plugging approved Yes 19

Plugging commenced 11-5 19 58

Plugging completed 11-10 19 58

Reason for abandonment of well or producing formation Oil Exhausted

If a producing well is abandoned, date of last production Oct. 1958 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Mr. Broadfoot

Name of Conservation Agent who supervised plugging of this well

Producing formation Kansas City Lime Depth to top 3367 Bottom 3488 Total Depth of Well 3699 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City Lime	@ Oil	3367	3488	8 5/8"	250	- -
				5 1/2"	3696	2,906'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 3699'.  
Plugging started 11-5-58. Finished 11-10-58.  
Plugged off bottom and sanded back to 3690'. Dumped 5 sacks cement.  
Worked pipe and loaded hole with water. Shot at 3000' and 2902'.  
Cleaned out cellar and shut off water. Squeezed well, using 20 sacks mud  
~~cement~~ and 100 sacks cement. Well completed.

12-17-58

RECEIVED  
STATE CORP  
DEC 17 1958  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1958

Betty S. Edman  
Notary Public.

My commission expires November 8, 1960.

PLUGGING  
FILE SEC 14 T. 21 R. 14W  
BOOK PAGE 137 LINE 16

Derby Drilling Company  
 352 North Broadway  
 Wichita 2, Kansas

J.W. Bird  
 c/o W.H. Bird  
 Union Nat'l. Bank Bldg.  
 Wichita, Kansas

Wright #1  
 NE/NE/NE 14-21-14W  
 Stafford County, Kansas

Elevation: 1923 D.F. - 1925 R.B.  
 Spudded: December 14, 1950  
 Rotary Completed: December 26, 1950  
 Cable Tools Completed:  
 Acid Treatment:  
 Initial Production:  
 Contractor: Derby Drilling Company

CASING RECORD

250' 8-5/8" O.D. 28# 8 Rd. Thd SS Casing cemented w/150 sacks cement.  
 3696' 5 1/2" O.D. 17# 8 Rd Thd SS Casing cemented w/125 sacks cement.

~~XXXXXXXXXX~~

DRILLERS LOG

Sand	0 to 200	Broken Lime.	1910 to 2035
Blue Shale	250	Lime	2135
Shale	255	Broken Lime	2435
Sand	280	Lime & Shale	2920
Red Rock	400	Shale	3028
Shale and Sand	825	Lime	3295
Anhydrite	853	Shale & Lime	3344
Shale & Shells	900	Lime	3557
Shale, Salt & Shells	1245	Broken Lime	3607
Shale & Shells	1620	Viola	3644
Shale	1630	Shale	3695
Sand	1645	Lime	3699 T.D.
Shale & Lime	1910		

3699 T.D. = 3697 D.F.

RECEIVED  
 CONSERVATION COMMISSION

OCT 18 1958

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 14 T 21 R 14W  
 BOOK PAGE 137 LINE 16