


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 14 Twp. 21S. Rge. 14 ~~W~~ (W)
Location as "NE/CNW/SW" or footage from lines NWSESW
Lease Owner Frank Black
Lease Name Rychlec Well No. 1
Office Address Box 250, McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed November 25 19 65
Application for plugging filed January 18 19 82
Application for plugging approved January 18 19 82
Plugging commenced January 18 19 82
Plugging completed January 21 19 82
Reason for abandonment of well or producing formation No commercial production
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3739 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|-------------------|
| | | | | 8 5/8" | 273' | cemented w/275 sx |
| | | | | 5 1/2" | 3736' | 1108' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand on bottom. 70' fill-up on sand. Mixed and dumped 5 sacks cement at 3655'. Pulled 1108' of 5 1/2".
Pumped 3 sacks hulls and 15 sacks gel. Pumped plug.
Pumped 140 sacks 50-50 Pos, 4% Gel, 3% Calcium chloride.

Name of Plugging Contractor, White & Ellis Drilling, Inc. License #209
Address Box 448, El Dorado, Kansas 67042

STATE OF KANSAS COUNTY OF BUTLER
Howard E. Russell (employee of ~~owner~~ contractor) or (owner or operator) of the above-described well, STATE CORPORATION COMMISSION on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
Box 448, El Dorado, Kansas 67042 (Address)
Witnessed before me this 11th day of February 19 82

FEB 12 1982

CONSERVATION DIVISION
Wichita, Kansas

Florence C. Toliaferro
STATE NOTARY PUBLIC
BUTLER COUNTY, KS.
My Appt. Exp. June 22, 1983

Florence C. Toliaferro
Notary Public.

CASING RECORD:
13 JTS 8-5/8"
28 1/2 PIPE

COMPANY: WESTERN PETROLEUM CO., INC.
CONTRACTOR: WESTERN PETROLEUM CO., INC.
COMMENCED: NOVEMBER 14, 1962
COMPLETED: NOVEMBER 25, 1962
ELEVATION: 1926 DF
1929 KB

113 JTS 5 1/2"
14 1/2 CASING

DESCRIPTION:
NW SE SW
SECTION 14-T21S-R14W
STAFFORD COUNTY, KANSAS

TOTAL DEPTH:
3739'

| FORMATION | FROM | TO | REMARKS |
|------------------------|------|------|---|
| CLAY, SAND | 0 | 40 | SPUDDED @ 12:30 PM. RAN 13 JTS 8-5/8" 28 1/2 USED PIPE, (268.86). SET @ 273' W/ 275 SXS 60x40 FORMIX, 2 SXS CC, 2 SXS AC. PLUG DOWN @ 5:45 PM. CEMENT CIRCULATED. |
| SAND, GRAVEL | 40 | 140 | |
| SHALE, SHELLS | 140 | 220 | |
| SHALE | 220 | 274 | |
| SHALE, SHELLS, RED BED | 274 | 285 | |
| ANHYDRITE | 285 | 290 | |
| SHALE AND SHELLS | 290 | 1570 | |
| SHALE AND LIME | 1570 | 1601 | |
| LIME | 1601 | 2035 | |
| LIME AND SHALE | 2035 | 2290 | |
| SHALE AND LIME | 2290 | 2620 | |
| LIME AND SHALE | 2620 | 2710 | |
| LIME, SAND | 2710 | 2831 | |
| SHALE AND LIME | 2831 | 3040 | |
| LIME AND SHALE | 3040 | 3103 | |
| LIME | 3103 | 3240 | |
| LIME AND SHALE | 3240 | 3302 | |
| SHALE AND LIME | 3302 | 3390 | |
| LIME | 3390 | 3645 | |
| LIME AND CHERT | 3645 | 3691 | |
| SHALE | 3691 | 3706 | |
| SHALE AND LIME | 3706 | 3739 | |
| RTD | 3739 | | |

DST #1 3550-65 OPEN 1 HOUR 15 MINUTES. FAIR STEADY BLOW. RECOVERED 510' VISIBLE GAS, 90' VERY HEAVY BLACK OIL, 60' FORMATION WATER. IBHP 960#/30MIN., FBHP 510#/30 MIN., IFF 15%, FFP 45%, HH 1940#.

DST #2 3652-3670 OPEN 35 MINUTES. WEAK BLOW FOR 5 MINUTES. RECOVERED 0' ROTARY MUD, FEW SPECKS OF OIL. IBHP 940#/30 MINUTES., FBHP 65#/30 MIN., IFF-FFP 0%. HH 1980#.

DST #3 3735-39 OPEN 1 HOUR 15 MINUTES. STRONG BLOW, RECOVERED 350' VISIBLE GAS, 1690' SLIGHT GASSY OIL. IBHP 1170#/30 MIN., FBHP 1170#/1 HOUR, IFF 35%, FFP 50%, HH 2010#.

RAN 113 JTS 5 1/2" 14 1/2 CASING. SET @ 3736 W/ 75 SXS 60x40 FORMIX (SALT SATURATED). PLUG DOWN @ 6:45 PM, 11/25/62.

ELECTRIC LOG TOPS

| | | |
|-----------|------|-------|
| ANHYDRITE | 830 | +1099 |
| HEEBNER | 3266 | -1337 |
| LANDING | 3094 | -1465 |
| D/KC | 3597 | -1668 |
| VIOLA | 3650 | -1721 |
| SIMPSON | 3696 | -1767 |
| ARBUCKLE | 3734 | -1805 |
| RTD | 3739 | -1810 |

STATE OF KANSAS }
COUNTY OF BARTON }

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

F. L. Copeland

SUBSCRIBED AND SWORN TO BEFORE ME THIS 27TH DAY OF NOVEMBER, 1962.

Ruth M. Kruckenberg
RUTH M. KRUCKENBERG, NOTARY PUBLIC

MY COMMISSION EXPIRES JUNE 13, 1966

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1962
CONSERVATION DIVISION
Wichita, Kansas