


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 27 Twp. 24 S Rge. 12 W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE NW

Lease Owner Cooperative Refinery Association

Lease Name Byer "B" Well No. 5

Office Address Drawer "C" - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 29 19 53

Application for plugging filed June 26 19 61

Application for plugging approved June 27 19 61

Plugging commenced July 10 19 61

Plugging completed July 17 19 61

Reason for abandonment of well or producing formation Non commercial

If a producing well is abandoned, date of last production March 19 61

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Viola Depth to top 3910 Bottom 3922 Total Depth of Well 4078 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	312/200sk	
				5-1/2"	4098w/175 sk	2766'9"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dug out cellar and deadman holes. Pump 35 barrels water, push plug to 3700'. Sanded from 3700' to 3670'. Dump 5 sax cement, unpack braden head, work pipe 21". Load hole with water. Shot pipe @2944'. Pump 100## pressure. Shot pipe @2860'. Pump 100## pressure. Shot pipe @2750', pump pressure to 850#, broke to 600#, spot 30 barrels oil. Working pipe loose. Pull 89 joints pipe, haul mud and mud hole to 270', 10' rock bridge, 270', 260', dump 3 sax cement. Bail hole down, test dry. Haul cement and water, dump 17 sax cement, mud to 40', 10' rock bridge, dump 10 sax cement. Well complete and approved by State Plugger, Frank Broadfoot.

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Comstock Casing Pulling Company
Address Stafford, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

John H. Nation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Nation

Drawer C - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1961.

My commission expires April 4, 1964 Notary Public.



File

15.185.12992.0000

WELLERS LOG

WELL # 15

BYER "B" #5

Elevation: 1879 D.F.
Casing: 2-5/8 O.D. w/ 200 cu.

Loc: SE NE NW
Sec: 27-24-12

SE NENE
SEC: 24-24-12W

5-1/2 O.D. w/ 175 cu.

Stafford County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Bud Edwards Drilling Co.

Cases: 6-27-53 Comp: 7-28-53
Total Depth: 1070

Top	Bottom	Description
1070	1065	Surface clay & shale
1065	1060	Sand
1060	1055	Shale w/ shells
1055	1050	Shale & Sand
1050	1045	Sand w/ shale streaks
1045	1040	Gravel
1040	1035	Red Rock
1035	1030	Shale & Shells
1030	1025	Red Red & Shells
1025	1020	Shale
1020	1015	Lime
1015	1010	Lime w/ shale
1010	1005	Lime
1005	1000	Lime w/ shale
1000	995	Lime
995	990	Lime & Shale
990	985	Lime
985	980	Lime w/ shale
980	975	Lime
975	970	Shale w/ lime streaks
970	965	Shale & lime shells
965	960	Shale w/ lime streaks
960	955	Lime
955	950	Lime & chert
950	945	Lime
945	940	Lime w/ cherty streaks
940	935	Shale
935	930	R.T.O.

(STATE OF KANSAS)
(COUNTY OF STAFFORD)

I hereby certify that the above is a true and correct copy of the log on the well #15, located SE NE NW of Sec. 27-24-12W, Stafford County, Kansas.

L. M. Collins

Subscribed and sworn to before me this 7-20 day of July, 1953.

L. G. E. Erdreich

My commission expires 7-20-53