

1 050213

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,987-0000

C N/2 SE, SEC. 9, T 21 S, R 12 W/4

1980 feet from ~~X~~/S section line

1320 feet from ~~W~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9263

Lease Name Setser Well # 1

Operator: Champion Petroleum, Inc.

County Stafford

Name & Address P. O. Box 251

Well Total Depth 5652 <sup>183.69</sup> feet

Ellinwood, KS 67526

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mustang Drilling, Inc. License Number 5652

Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 2:00 am Day: 9 Month: May Year: 19 84

Plugging proposal received from Gib Overby

(company name) Mustang (phone) 316-348-5713

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 50 sx cement

2nd plug at 300' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by Richard M. Lucas  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:15 am Day: 9 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement, 2nd plug at 300' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, Plug water well

with 5 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(If (copy) / (date) observe this plugging.

Signed Richard M. Lucas  
(TECHNICIAN)

DATE 5-21-84

INV. NO. 1567  
5-9