

1 050890

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,428-0000
100' N of _____
W/2 W/2 SE, SEC. 13, T 21 S, R 12 W/E
1420 feet from S section line
2310 feet from E section line
Lease Name Kasselman Well # 4
County Stafford 114.79
Well Total Depth 3532 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address Route 1, Box 183-B
Great Bend, KS 67530

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 205 E. Central, Suite 120, Wichita KS 67202

Company to plug at: Hour: 8:15 p.m. Day: 6 Month: 4 Year: 1987

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company (phone) 316-792-1171

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 584'

1st plug at top of Arbuckle with 50 sx cement, 2nd plug at Base Anhydrite with 50 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1987

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:20 p.m. Day: 6 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 330' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did/did not) observe this plugging.

DATE 4-9-87

Signed Richard Lacey
(TECHNICIAN)

INV. NO. 16532

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date April 2, 1987 month day year 87

API Number 15-185-22,428-0000

OPERATOR: License # 6039 Name L. D. DRILLING, INC. Address Route 1, Box 183-B City/State/Zip Great Bend, Kansas 67530 Contact Person L. D. Davis Phone 316/793-3051

100'N of W/2 W/2 SE Sec. 13 Twp. 21 S, Rg. 12 East W/2 W/2 SE 1420 2310 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5929 Name DUKE DRILLING CO., INC. City/State Great Bend, Kansas 67530

Nearlest lease or unit boundary line 330 feet County Stafford Lease Name Kasselman Well # 4 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 130 Depth to bottom of usable water 250 Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 300 Conductor pipe required Projected Total Depth 3600 feet Formation Arbuckle

Well Drilled For: X Oil SWD Well Class: X Infield Type Equipment: X Mud Rotary Gas Inj Pool Ext. Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plug eventually plugging hole to KCC specifications. Date April 1, 1987 Signature of Operator or Agent Sally R. Myers Title Agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 275 feet per Alt. This Authorization Expires 10-2-87 Approved By 4-1-87

SPUD 4-2-87 300+ 8 5/8 Reicher

100'N of W/2 W/2 SE Sec. 13 Twp. 21 S, Rg. 12 East W/2 W/2 SE

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 3550 feet depth with 60/40 Pozmix, 6% gel 2nd plug @ 350 base Anhydrite feet depth with 60/40 Pozmix, 6% gel 3rd plug @ 330 feet depth with 60/40 Pozmix, 6% gel 4th plug @ 40 feet depth with 60/40 Pozmix, 6% gel 5th plug @ 15 feet depth with 60/40 Pozmix, 6% gel (2) Rathole with 15 (b) Mousehole with

PUSHER TD 5532 FORMATION Arb. SURFACE PIPE 8 5/8 @ 300 ANHYDRITE 584 ELEVATION STARTING TIME & DATE 8:15 COMPLETION TIME & DATE 10:20 1st PLUG @ 600 FT. W/ 50 SX 2nd PLUG @ 330 FT. W/ 50 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Halliburton TECHNICIAN

60/40 690

RECEIVED STATE CORPORATION COMMISSION

APR 9 1987

CONSERVATION DIVISION Wichita, Kansas