

1 120944

15-145-00103-00-00

7-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 7/17/59
NW NW SE, SEC. 31, T. 23 S, R. 16 W
2310 feet from S section 11
2310 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License / NONE-LANDOWNER
Operator: Bill Schartz
Name:
Address 1118 State St.
Larned, KS 67550

Lease Name Schartz Well # 1
County Pawnee
Well Total Depth 4312 140.14 ft
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 10 a.m. Day: 22 Month: 7 Year: 1994
Plugging proposal received from Art Merrick
(company name) _____ (phone) _____

vera: 4 1/2" at 4299' w/150 sx cement, Perfs at 4210-20'
1st plug pump in 4 1/2" casing with 200 lbs. hulls, 30 sx cement, gel spacer to 1000' and circulate cement from 1000' through tubing.

2nd plug pump in 8 5/8" X 4 1/2" annulus with 150 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 15 1994
STEVE DUTTON DIVISION
WICHITA, KS
TECHNICIAN

Plugging Proposal Received by Steve Dutton

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4 p.m. Day: 22 Month: 7 Year: 1994

ACTUAL PLUGGING REPORT Ran tubing in 4 1/2" casing to 3730' and pumped in 30 sx cement, Pulled tubing to 1000' and pumped through tubing with 285 sx cement. Cement did not circulate in 8 5/8" X 4 1/2" annulus. Capacity of the 4 1/2" casing from 1000' is 50 sx. 265 sx cement were squeezed through a hole or holes in the 4 1/2" casing at an unknown depth above 1000'. Pulled all tubing and topped the 4 1/2" casing with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-14-94
INV. NO. 41218

Signed _____
TECHNICIAN

7-22 NOV 16 1994