

To: 1 041209
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION 100'
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-145-21,422-0060
E SW SW SW SEC. 32, T 23 S, R 16 W/E
330 feet from S section line
4850 feet from E section line

10-2

TECHNICIAN'S PLUGGING REPORT
Operator License / 8061
Operator: Oil Producers, Inc. of Kansas
Name: P.O. Box 8647
Address: Wichita, KS 67208-8674

Lease Name Wurm Well / 1
County Pawnee 141.37
Well Total Depth 4350 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well Gas Well Input Well SMD Well O&A
Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11 a.m. Day: 2 Month: 10 Year: 19 96

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4349' w/100 sx cement, PBTD 4310', Perfs at 4237-81'
1st plug sand back to 4187' and dump 4 sx cement on top of sand through bailer,
2nd plug spot 50 sx cement at 1100',
3rd plug spot 60 sx cement at 390',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 p.m. Day: 2 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4187' and dumped 4 sx cement on top of sand bridge through bailer,

Spotted plugs through 4 1/2" casing:
2nd plug at 1100' with 50 sx cement,
3rd plug at 390' with 60 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1988' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-8-96
INV. NO. 46670

Signed: *Kevin Strube*
(TECHNICIAN)