

1 120235

3-24

212 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,168,0000
C SE NE, SEC. 32, T 23 S, R 16 W&E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566

Lease Name Berscheidt Well # 1

Operator: Leben Oil Corporation

County Pawnee 145.44

Name &

Address P.O. Box 21468

Well Total Depth 4475 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 24 Month: 3 Year: 19 89

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pullers (phone) 316-938-2457

were: 4 1/2" at 4468.5' PBT 4364' Perfs at 4182-4198.5' (4 sets)

1st plug sand back to 4130' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

MAR 28 1989

Plugging Operations attended by Agent?: All Part _____ None _____

Operations CONSERVATION DIVISION
Wichita, Kansas Hour: 3:30 p.m. Day: 24 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4130' and dumped 4 sx cement
on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2400' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-30-89

Signed Richard Lacey
(TECHNICIAN)

INV. NO. 24298