

1091022

TO: STATE CORPORATION COMMISSION

API NUMBER 15-145-21,451-6000
C W/2 SE SEC. 36, T 23 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JAHAMA WELL # 1-36

TECHNICIAN'S PLUGGING REPORT 11-1

COUNTY PAWNEE 135.68

OPERATOR LICENSE # 3180

WELL TOTAL DEPTH 4175 FEET

OPERATOR: DEUTSCH OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 2553' WITH 125 SX

NAME AND ADDRESS 8100 E 22ND N BLDG 600, STE D SURFACE CASING: SIZE 8 5/8" @ 263' WITH 210 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 12:15 PM DAY: 01 MONTH: 11 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BRYAN FRENZL

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 2030-36

1ST PLUG SAND TO 1965' WITH 4 SX CEMENT ON TOP. SHOT PIPE AT 1165'. 2ND PLUG PULL TO 1005' SPOT 10 SX GEL AND 50 SX CEMENT. 3RD PLUG PULL TO 332' SPOT 60 SX CEMENT. 4TH PLUG PULL TO 40' CIRCULATE CEMENT TO SURFACE. STAYED FULL.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 01 MONTH: 11 YEAR: 1999

ACTUAL PLUGGING REPORT _____

1ST PLUG SAND TO 1965' WITH 4 SX CEMENT ON TOP. SHOT PIPE AT 1165'. 2ND PLUG PULL TO 1005' SPOT 10 SX GEL AND 50 SX CEMENT. 3RD PLUG PULL TO 332' SPOT 60 SX CEMENT. 4TH PLUG PULL TO 40' CIRCULATE CEMENT TO SURFACE. STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION

11-9-99 NOV - 9 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1165' OF 4 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 12/3

SIGNED [Signature]
(TECHNICIAN)

FORM CP-2/3

INV. NO. 60903

AWY