

1 050847

15-145-06523-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

SE SE NE, SEC. 36, T 23 S, R 16 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258

Lease Name Peters Well # 1

Operator: Messman-Rinehart Corporation
Name & Address 500 Bitting Building
Wichita, KS 67202

County Pawnee 134.23

Well Total Depth 4130 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Co. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 6 Month: 10 Year: 19 86

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling Co. (phone) 316-938-2457

were: 5 1/2" at 4130 PBSD 3970' Perfs 3819-24'

1st plug sand to 3750' and dump 5 sx cement on top of sand through bailer

2nd plug pump down with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release plug and pump 100 sx cement

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 6 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3750' and dumped 5 sx cement on top of sand through bailer

2nd plug pumped down 8 5/8" with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug, and pumped 100 sx cement

RECEIVED STATE CORPORATION COMMISSION CONS. DIV. WICHITA, KS

Maximum pressure 500 psi and shut in 50 psi. OCT 8 1986

Remarks: Recovered 2200' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied. (if additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 10-9-86

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 15119