

To: 1 120621
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-13 15.185.00939.0001 65R
API NUMBER 15- Docket #D-10,302

SW SW SW, SEC. 14, T 21 S, R 14 W/E
330 feet from S section line
4950 feet from E section line
Lease Name Rychlec Well # 3
County Stafford 123.17
Well Total Depth 3790 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 265

TECHNICIAN'S PLUGGING REPORT
Operator License # 5357
Operator: Frank J. Black Estate
Name &
Address 600 W. Washington
McPherson, KS 67460

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 13 Month: 9 Year: 19 91

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3780' w/125 sx cement, 4 1/2" liner set and cemented at 3780', 10' open hole
Ran tubing to 3380' and pump 40 sx cement in 4 1/2" casing,
Pull tubing to 1080' and circulate cement,
4 1/2" & 5 1/2" casing parted at 1050',

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 13 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug 109 joints of 2 3/8" tubing to 3380' and pumped 40 sx
cement, layed down 74 joints of 2 3/8" tubing and circulate at 1080' with 100 sx cement,
layed down all tubing and filled 4 1/2" casing with 15 sx cement.
Pumped in 8 5/8" X 5 1/2" annulus with 160 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Pumping pressure 0-300 psi and shut in 100 psi.

SEP 18 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. CONSERVATION DIVISION
Wichita Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED
I will observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 10-4-91
INV. NO. 33258