

To: 1 061016  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
203 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-28-87 15.185.20775.0000  
API NUMBER 13-NA  
C NE SW, SEC. 14, T 21 S, R 14 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Lease Name Rychlee Well # 1  
County Stafford 122.62

Operator: Knighton Oil Company, Inc.  
Name & Address 710 Petroleum Building  
Wichita, KS 67202

Well Total Depth 3773 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 28 Month: 9 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

were: 5 1/2" at 3757' Perfs at 3773' squeezed at 375'

1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,

2nd plug shoot 5 1/2" at 820' and squeeze with 165 sx cement,

3rd plug fill 8 5/8" with cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 28 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand through bailer,

2nd plug shot 5 1/2" at 820' and squeezed with 165 sx cement,

3rd plug filled 8 5/8" with no cement - pressured up to 500 lbs. immediately.

Maximum pressure 350 psi and shut in 350 psi on 5 1/2".

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1987  
9-29-87  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I hereby acknowledge and agree to reserve this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 10-6-87

INV. NO. 18391