

1 120622
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5357
Operator: Frank J. Black Estate
Name &
Address 600 W. Washington
McPherson, KS 67460

9-13
API NUMBER 15- 185-20,977.0000 *let R*

NE SW SW, SEC. 14, T 21 S, R 14 W/E
990 feet from S section line
4290 feet from E section line

Lease Name Rychlec Well # 7
County Stafford 121.71
Well Total Depth 3745 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 13 Month: 9 Year: 19 91

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3743' w/100 sx cement, Open hole
1st plug sand back to 3690' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:45 a.m. Day: 13 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3690' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2020' of 5 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION
9-18-91
SEP 18 1991

(If additional description is necessary, use BACK of this form.)
I (or my agent) observe this plugging.

INVOICED
DATE 10-4-91
INV. NO. 33257

Signed Steve Middleton
(TECHNICIAN)