

1  
080350

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-20,871-0000

990 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Rychlec "B" Well # 1

Operator: L. D. Davis  
Name & Address R. R. 1, Box 183B  
Great Bend, KS 67530

County Stafford 123.18

Well Total Depth 3790 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 307 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:00 am Day: 22 Month: March Year: 19 85

Plugging proposal received from Bob Strube

(company name) D W & W (phone) 316-587-3361

were: 4 1/2" at 3789'

1st plug set cast iron bridge plug at 3416' with 4 sx cement

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging orders given by Robert B. Tarbutton

Plugging Proposal Received by J. A. McJ  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 pm Day: 22 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set cast iron bridge plug at 3416' with 4 sx cement,

2nd plug squeezed well with 2 1/2 sx hulls, 10 sx gel 50 sx cement, 10 sx gel, 1 1/2 sx hulls and 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 28 1985  
3-28-85

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 300 and shut in 250 psi

Remarks: Recovered 2500' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

(did / observe this plugging.

DATE 4-3-85

Signed J. A. McJ  
(TECHNICIAN)

INV. NO. 7494