

To: 1 051593 10-24
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-21,147.0000 309 R
C NE NE, SEC. 33, T. 21 S, R 31 W/E
660 feet from N ~~S~~ section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4629
Operator: Brito Oil Company, Inc.
Name & Address: 200 E. 1st, Ste. 208
Wichita, KS 67202

Lease Name Nelson Well # 1-33
County Finney 157.95
Well Total Depth 4860 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 24 Month: 10 Year: 19 92

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 2140-63'
1st plug at 2160' with 50 sx cement, 2nd plug at 1450' with 80 sx cement,
3rd plug at 700' with 40 sx cement, 4th plug at 250' with 40 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:45 a.m. Day: 24 Month: 10 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,
2nd plug at 1450' with 80 sx cement,
3rd plug at 700' with 40 sx cement,
4th plug at 250' with 40 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel $\frac{1}{4}$ # floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 11-20-92
INV. NO. 36826

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1992

CONTA, Kansas

EFFECTIVE DATE: 10-6-92

DISTRICT # 1

SSA? Yes, U, No

State of Kansas 15. 055-21,147.0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 5 1992
month day year

NE NE Sec 33 Twp 21 S. Rg 31 East
West

OPERATOR: License # 4629
Name: Brito Oil Company, Inc.
Address: 200 E. First, Suite 208
City/State/Zip: Wichita, KS 67202
Contact Person: Raul E. Brito
Phone: 316-263-8787

660' feet from ~~South~~ North line of Section
660' feet from East / ~~West~~ line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Finney
Lease Name: Nelson Well #: 1-33
Field Name: Wildcat

CONTRACTOR: License #: 6033
Name: Murfin Drilling Company

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Morrow, Mississippi
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2898 feet MSL

Well Drilled For: Well Class: Type Equipment:
X. Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 1425'
Surface Pipe by Alternate: 1 .. X 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: None
Projected Total Depth: 4800
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well farm pond .. X other

If OUVO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:

Directional, Biviated or Horizontal wellbores? yes X no
If yes, true vertical depth:
Bottom Hole Location:

AFFIDAVIT

200' Alt. II Req.

Exp. 4/1/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Rodney Jones
SPUD DATE 10-16-92 INIT. St
LENGTH SURFACE PLANNED 200'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/4" @ 218 CONDUCTOR
ANHYDRITE T- 2140 B- 2163 ELEVATION
2708
TD 4860 FORMATION MISS
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2160 Ft. W/ 50 SX
1/2 Base Anyh. @ 1450 Ft. W/ 80 SX
1/2, 1/2 Plug @ 700 Ft. W/ 40 SX
Bottom Surface @ 250 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN R.L. DATE 10-22-92 Hauling
TYPE OF CEMENT 60/40 60/40 60/40 1/4 Plug
STARTING TIME 1:00 (AM/PM) DATE 10-24-92
COMPLETION TIME 3:45 (AM/PM) DATE 10-24-92
CEMENT COMPANY Atlantic