

6-26-88

336

R

To: 1 061113  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-055-20,798.0000

660 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4779  
Operator: North American Resources Company  
Name:  
Address 16 East Granite  
Butte, MT 59701

Lease Name Richter Well # 29-1  
County Finney 162.50  
Well Total Depth 5000 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382  
Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 5 p.m. Day: 26 Month: 6 Year: 19 88

Plugging proposal received from Jack Pepper

(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2140'

1st plug at 2980' with 100 sx cement, 2nd plug at 2140' with 50 sx cement,  
3rd plug at 1300' with 100 sx cement, 4th plug at 490' with 50 sx cement,  
5th plug at 40-0' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 9:45 p.m. Day: 26 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2980' with 100 sx cement, 2nd plug at 2140' with  
50 sx cement, 3rd plug at 1300' with 100 sx cement,  
4th plug at 490' with 50 sx cement,  
5th plug at 40-0' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 5 1988 7-5-88

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. CONSERVATION DIVISION  
(If additional description is necessary, use BACK of this form.)

INVOICED (SEE) did not observe this plugging.

DATE 7-19-88

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 21434

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 1988 month day year

API Number 15-055-20, 798-0080

OPERATOR: License # 4779
Name North American Resources Company
Address 16 East Granite
City/State/Zip Butte, MI 59701
Contact Person Leo A. Heath
Phone (406) 723-5421

C W 1/2 SW SW Sec. 29 Twp. 21 S, Rg. 31
660 Ft. from South Line of Section
4950 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Finney

CONTRACTOR: License # 5382
Name Cheyenne Drilling, Inc.
City/State Garden City, KS
Well Drilled For: 316 Well Class: Type Equipment:
Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Richter Well # 29-1
Ground surface elevation 2911 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 200'
Depth to bottom of usable water 1300'
Surface pipe by Alternate: 1-2 X
Surface pipe planned to be set 450'
Conductor pipe required No
Projected Total Depth 5000 feet
Formation Mississippian

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications.

Date 5/16/88 Signature of Operator or Agent Title Mgr. Eng. and Oper.

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt.
This Authorization Expires 4-24-88 Approved By 5-24-88

EFFECTIVE DATE: 5-29-88

AUG II

Spud 6-18-88
Set @ 458

C W 1/2 SW SW Sec. 29 Twp. 21 S, Rg. 31 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (e.g., 2900, 2100, 1300, 450, 40, 15), feet depth with, and sxs of Class 'G' cement.

Vertical list of well parameters: PUSHER 5ALC Pepper, TD 5000 FORMATION, SURFACE PIPE 8 3/4 @ 458, ANHYDRITE 2140 ELEVATION 6-26-88, STARTING TIME & DATE 5:00 PM, COMPLETION TIME & DATE 9:45 PM, 1st PLUG @ 2980 FT. W/ 100 SX, 2nd PLUG @ 2140 FT. W/ 50 SX, 3rd PLUG @ 1300 FT. W/ 100 SX, 4th PLUG @ 450 FT. W/ 50 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Ball-Burster, TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION JUL 1 1988 CONSERVATION DIVISION Wichita, Kansas