

1051788

3-11

API NUMBER 15-055-21,270-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4779
Operator: North American Resources Co.
Name: _____
Address: 16 East Granite
Butte, MT 59701

App. S/2 SE SE, SEC. 29, T. 7 N. S. R. 31 W. XX
330 feet from S section line
660 feet from E section line
Lease Name Isaac Farms Well # 29-2
County Finney
Well Total Depth 4900 159.25 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 8 a.m. Day: 11 Month: 3 Year: 19 94

Plugging proposal received from Tony Martin

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2126-96'

1st plug at Hugoton/Council Grove with 100 sx cement,

2nd plug at 2250' with 50 sx cement, 3rd plug at 1600' with 50 sx cement,

4th plug at 850' with 50 sx cement, 5th plug at 275' with 50 sx cement,

6th plug at 40' with 10 sx cement, 7th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 11 a.m. Day: 11 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 2980' with 100 sx cement,

2nd plug at 2250' with 50 sx cement, 3rd plug at 1600' with 50 sx cement,

4th plug at 850' with 50 sx cement,

5th plug at 275' with 50 sx cement,

6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(I did / ~~did not~~) observe this plugging.

DATE 3-28-94

INV. NO. 40167

3-11

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1994
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 1-10-94

State of Kansas

ALL BLANKS MUST BE FILLED

SGA7... Yes... No Must be approved by the K.C.C.

NOTICE: INTENTION TO DRILL DIST 1
five (5) days prior to commencing well

Expected Spud Date: 1 month 2 day 94 year
Spot 5/2 SE SE Sec 29 Twp 21 S, Rg 31 East West

OPERATOR: License # 04779
Name: North American Resources Co.
Address: 16 East Granite
City/State/Zip: Butte, MT, 59701
Contact Person: Jim Else
Phone: 406-496-5292

660' 330' feet from South North line of Section
660' feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Finney

CONTRACTOR: License # 30684
Name: Abercrombie RTD, Inc.

Lease Name: Isaac Farms Well #: #29-2
Field Name: Wildcat

Is this a Prorated/Spaced Field? yes ..X.. no
Target Formation(s): Mississippi

Nearest lease or unit boundary: 660' 330'
Ground Surface Elevation: Unknown feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OVVV ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

Water well within one-quarter mile: yes X.. no
Public water supply well within one mile: yes X.. no

Depth to bottom of fresh water: 80' 100'
Depth to bottom of usable water: 200' 1480'

Surface Pipe by Alternate: 1 X.. 2
Length of Surface Pipe Planned to be set: 225'

Length of Conductor pipe required: 0
Projected Total Depth: 4900'

Formation at Total Depth: Mississippi
Water Source for Drilling Operations:

If OVVV: old well information as follows:
Operator: N/A
Well Name:
Comp. Date: Old Total Depth

... well ... farm pond X other
DWR Permit #: Will File

Will Cores Be Taken?: yes ... no X
If yes, proposed zone: N/A

Directional, Deviated or Horizontal wellbore? yes ... no
If yes, true vertical depth:
Bottom Hole Location:

AFFIDAVIT

225' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will RECEIVED K.S.A. 55

Pusher Tony SPUD DATE 3-3-94 INIT. CA
LENGTH SURFACE PLANNED 225'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 1 3/8" @ 237' CONDUCTOR
ANHYDRITE T- 2126 B- 2196 ELEVATION
TD 4900 FORMATION Miss
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 2480 Ft. W/ 100 SX
Anhydrite Base @ 2250 Ft. W/ 50 SX
1/2 Base Anyh. @ 1600 Ft. W/ 50 SX
1/2, 1/2 Plug @ 850 Ft. W/ 50 SX
Bottom Surface @ 275 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN CA DATE 3-2-94 Hauling
TYPE OF CEMENT 6/10 670
STARTING TIME 3-11-94
COMPLETION TIME 3-11-94
CEMENT COMPANY Wichita-Kansas
RECEIVED
STATE CORPORATION COMMISSION
MADE 1 5 1994
1-act witnessed part