

To: 1 080082  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-055-20,198.0000  
App. S/2, SEC. 24, T 21 S, R 32 W/EX

TECHNICIAN'S PLUGGING REPORT

11-14

Operator License # 3871

1450 feet from S section line  
2310 feet from E section line

Operator: Hugoton Energy Corporation  
Name:  
Address: 301 N. Main, Ste. 1900  
Wichita, KS 67202

Lease Name Winters Well # 1-A  
County Finney 89.37

Well Total Depth - 2750 feet

Conductor Pipe: Size - feet

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 2:40 p.m. Day: 14 Month: 11 Year: 19 96

Plugging proposal received from Joe Brougher

(company name) Hugoton Energy Corporation (phone) 316-287-3811

Work: 4 1/2" at 2750' w/550 sx cement, Perfs at 2700-2710'

1st plug pump down 4 1/2" with 250 lbs. hulls and 100 sx cement.

2nd plug pump 2 bbls. down 8 5/8" X 4 1/2".

Plugging Proposal Received by Kevin Strube  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:10 p.m. Day: 14 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 250 lbs. hulls and 100 sx cement.  
Maximum pressure 700 psi and shut in 700 psi.

2nd plug pumped down 8 5/8" X 4 1/2" with 2 bbls. cement. Pressured up to 300 psi.

11-21-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Kevin P. Strube  
(TECHNICIAN)

DATE 11-22-96

INV. NO. 47029