

To: 1 080111 3-12
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-055-20,195.0000
App. C SE, SEC. 10, T 21 S, R 32 W/X
1250 feet from S section line
1470 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4058
Operator: American Warrior, Inc.
Name:
Address: P.O. Box 399
Garden City, KS 67846

Lease Name Koster Well # 1
County Finney 89.57
Well Total Depth 2756 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 11:30 a.m. Day: 11 Month: 3 Year: 19 97

Plugging proposal received from Kevin Wiles
(company name) American Warrior, Inc. (phone) 316-275-2963

Work: 4 1/2" at 2756' w/550 sx cement, PBTD 2754', Perfs at 2706-16'
1st plug pump 200 sx hulls and 100 sx cement to bottom,
2nd plug pump 70 sx cement at stub,
3rd plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:30 p.m. Day: 12 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 100 sx cement. Maximum pressure 1800 psi and shut in 1000 psi.

Ran wireline, tagged top of cement at 481'. Shot off at 442'.
2nd plug pumped 70 sx cement at 442',
3rd plug pulled casing out of hole and topped off with 10 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 442' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE MAR 21 1997
INV. NO. 47779
3-12

Signed Kevin P. Strube
(TECHNICIAN)

RECEIVED
KANSAS CORP COM
MAR 20 11 30 AM '97