

To: 1 080112 3-12
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 055-20,207. 0000
C SW , SEC. L 34 , T 21 S, R 32 W/EX
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4058
Operator: American Warrior, Inc.
Name:
Address P.O. Box 399
Garden City, KS 67846

Lease Name Atkinson Well # B-1
County Finney 88.85
Well Total Depth 2734 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mikes Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 9:30 a.m. Day: 12 Month: 3 Year: 19 97

Plugging proposal received from Kevin Wiles
(company name) American Warrior, Inc. (phone) 316-275-2963

Work: 4 1/2" at 2734' w/550 sx cement, PBDT 2725', Perfs at 2706-16, 2674-81'
1st plug pump 300 lbs. hulls and 100 sx cement to bottom,
2nd plug pump 50 sx cement at stub,
3rd plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 6:30 p.m. Day: 12 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. ahead and 200 lbs. hulls mixed in 100 sx
cement. Maximum pressure 100 psi. Shut in.

2nd plug shot at 590', not free, shot at 420', not free, shot at 322', free. Pumped
50 sx cement,
3rd plug pulled casing out of hole and topped off with 20 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 322' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or XXXXXXXX) observe this plugging.

DATE MAR 21 1997
INV. NO. 47481
3-12

Signed Kevin D Strube
(TECHNICIAN)

RECEIVED
KANSAS CORP COM
MAR 20 11:11 AM '97