

3-14-88

API NUMBER 15-185-20,984-0000

To: 1 120082
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NW, SEC. 33, T. 24 S, R. 14 W/4E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635

Lease Name H.J. Waters Well # 1 A

Operator: Great Bend Casing Pullers, Inc.
Name & Address P.O. Box 768
Great Bend, KS 67530

County Stafford 141.38

Well Total Depth 4350 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 14 Month: 3 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4340' PBSD 4320' Perfs at 4113-3838' (5 sets)

1st plug sand back to 3790' and dump 4 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls,
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 14 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3790' and dumped 4 sx cement on top of
sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Pumping pressure 0-700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2047' of 4 1/2" casing. Top of plug @ 80'
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

MAR 17 1988
CONSERVATION DIVISION
Wichita, Kansas

Signed Duane Rankin
(TECHNICIAN)

DATE 3-21-88

INV. NO. 20139