

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145 -20171-0000 (of this well)

Operator's Full Name Sterling Drilling Co.
Complete Address Box 129, Sterling, Kansas 67579
Lease Name Wurm (OWWO) Well No. 2
Location C E/2 SE Sec. 32 Twp. 23 Rge. (E) (W) 16
County Pawnee Total Depth 2931'
Abandoned Oil Well Gas Well XX Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 3:45 P Day 8 Month 7 Year 1977

The above well was plugged as follows:

Total Depth 2931' 8 5/8 csg set 317' cwc 275 sk.
4 1/2 csg set 2889' cw 300 sk cem.
4 1/2 csg PBTD 2250' with perf. (2176'-2182')
Filled 4 1/2 csg with sand (2250'-2150') dumped 3 sk cem W/dump bailer. (2150'-2120')
Cutoff & recovered 1900' of 4 1/2 csg.
Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs
hulls- cementing plug & 120 sk 60/40 poz & shutin. FPP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *P. E. Massey*
Well Plugging Supervisor

DATE 7-12-77

INV. NO. 5460 W