

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

15-145-00383-0000

FILE NO. 119-19

LOCATION 5W-5W-5W

SEC. 32 TWP. 23 RGE. 16 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease A. Wurm

Operator Petroleum Management Address Central Bldg. Wichita, Ks.

Field _____ County Pawnee

Total Depth 4596 Feet.

Plugging Contractor Morgan Well Plugging Serv.

Plugging Contractor's License No. 43

Address Hutchinson, Kans.

(Describe briefly the manner in which the well was plugged)

*Surface pipe 8 7/8" @ 190' c.w.c. 5 1/2" casing set
4359' w/ 150 sv cem. Plugged back to 4300'
Top perf. 4262' Filled back with chat to
4250' and dumped 5 sv cem. Ripped off
and pulled 5 1/2" casing. Pumped 15 sv fresh
fill mud. Plug and 85 sv cem. Filling hole
and surface from 255' to base of cellar with cem.
Pumping by Sun Cem. Co.*

Warren H. Harner
District Conservation Agent

Date May 28, 1955

STATE CORPORATION COMMISSION

MAY 30 1955 5-30-55

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 32 TWP. 23 RGE. 16 W
BOOK PAGE 119 LINE 19