

KANSAS

Form CP-3  
RECEIVED 6-4-68  
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

DEC - 5 1979

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 145 - 26465-0000 (of this well)

Operator's Full Name ZENITH DRILLING CORPORATION  
Complete Address 505 FOURTH FINANCIAL CENTER - WICHITA, KS. 67202  
Lease Name WURM Well No. #1  
Location C-NW-SW. Sec. 34 Twp. 23 Rge. 16 (E) (W) W  
County PANNEE Total Depth 4205 FE.  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor GLENN'S CASING PULLING INC  
Address BOX 413 ELLENWOOD, KS. 67526 License No. 832  
Operation Completed: Hour 12:15 PM Day 4<sup>th</sup> Month DEC Year 1979

The above well was plugged as follows:

8 5/8" 242 FE SR CUC. w/225 ST -> 4 1/2" SET AT 4105 FE w/125 ST  
PERF'S - 4115 FE - PLUG. BACK. 4106 FE - BOTTOM SAND TO 3950 FE  
AND 4 ST CMT. - SHOT PIPE (4) TIMES RECOVERED 3000 FE  
ORDERED 155 ST 50/50 POZ MIX 4% GEL -> 30 ST GEL, - 6 ST HULLS -> 8 5/8" PLUG.  
PUT IN 8 5/8" WITH PUMP TRUCK. - 3 ST HULLS - 25 ST CMT. - 30 ST GEL,  
RELEASE PLUG. AND 130 ST CMT. MAX PRESSURE 200 LBS.  
CEMENTED BY APPLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12-6-79  
INV. NO. 1020-W

Signed: Marcia Schmidt  
Well Plugging Supervisor