

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Messman-Rinehart Oil Company 15-145-00018-0D-01

Complete Address: 1432 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Wurm "A" Well No. 1

Location NW NW NE Sec. 34 Twp. 23 Rge. 16 (E) (W) XX

County Pawnee Total Depth 4196'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30P Day 4 Month 12 Year 1968

The Above well was plugged as follows:

Total Depth 4196' 8 5/8 csg set at 342' cwc

4 3/8 csg set at 4178' cw 100 sc cement.

4 1/2 csg PBTD 4146' and perf. (4110-16)

Filled 4 1/2 csg with sand to 4100' and dumped 3 sc cmt. with dump bailer.

Pushed wood plug to 1801' Poured 10 gal sand and dumped 3 sc cement with dump bailer.

Shutoff and recov. 1723' of 4 1/2 csg.

Pumped thru 8 5/8 plg container with 20 sc gel, plug and 100 sc 50-50 poz cmt. W/6%

total gel. Max. pres. 250 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 12/6/68

INV. NO. 8952-W