

KANSAS

*AL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 29 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name K & E Drilling, Inc. 15-145-20237-0000  
Complete Address 816 Union Center Wichita, Kansas 67202  
Lease Name W. L. Schartz Well No. 1  
Location SW SW NW Sec. 35 Twp. 23 Rge. (E) (W) 16  
County Pawnee Total Depth 4214'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Russ Casing Pulling  
Address Box 1082 Great Bend, Kansas 67530 License No. 623  
Operation Completed: Hour 10:15 A Day 28 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 4214' 8 5/8 csg set at 421' cwc  
4 1/2 csg set at 4212' cw 100 sk cmt.  
4 1/2 csg PBTD 4173' with perf. (4084-4088)  
Filled 4 1/2 csg W/sd (4050-4173) Dumped 4 sk cmt W/dump bailer. (4010-4050)  
Cutoff and recovered 2195' of 4 1/2 csg.  
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug  
and pumped 100 sk reg poz 6% total gel. SI pres. 200 lbs. By Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3/1/72  
INV. NO. 5249-4