

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

JAN 11 1965

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Circle Oil CompanyComplete Address: 816 Bitting Bldg., Wichita, KansasLease Name Wright Well No. # 1Location SW NE NE Sec. 14 Twp. 21 Rge. 14 (E) (W) WCounty Stafford Total Depth 3720Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Terrel Drilling & ProducingAddress: Box 606, Russell, Kansas License No. Operation Completed: Hour 5:15PM Day 10th Month Jan. Year 1965

The Above well was plugged as follows:

318' of 8 5/8" surface pipe, cemented with 250 sacks. Hole was over
filled with drilling mud to 40'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 275', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls and dry cement on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 1-12-65INV. NO. 513-WSigned: Archie Elving
Well Plugging Supervisor