

15.185.10788.0000

Form CP-3  
Rev. 6-4-68

KANSAS

*AL*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Frank J. Black  
Complete Address Box 150 McPherson, Ks  
Lease Name Rychlec Well No. 2  
Location SE/NE/SW Sec. 14 Twp. 21 Rge. 14 (E)     (W) W  
County Stafford Total Depth 3955  
Abandoned Oil Well X Gas Well     Input Well     SWD Well     D & A      
Other well as hereafter indicated      
Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Ks License No. 399  
Operation Completed: Hour 2:00 PM Day 29 Month 10 Year 1971

The above well was plugged as follows:

291 ft 8 5/8 surface pipe cemented with 285 sacks. 3825 ft 5 1/2 long  
string cemented with 100 sacks. Top perf. 3760 ft. Sand back to  
3725 ft, 5 sacks cement with bailer. Pulled 2630 ft 5 1/2. Pump 5 sacks  
hulls, 20 sacks gel., 100 sacks cement to surface.  
Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 11/2/71  
INV. NO. 4564-44

Signed: G. Russell Bikerstein  
Well Plugging Supervisor