

15.075.20058.0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dare Gas Inc.

Complete Address Box 544, Liberal, Kansas

Lease Name Howell Well No. 1

Location C NW SE Sec. 19 Twp. 21 Rge. 42 (E) (W)

County Hamilton Total Depth 2850'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 21 Month 9 Year 1973

The above well was plugged as follows:

8 5/8" to 200' circulated w/ cement. 4 1/2" to 2850' cemented.

Top perforations 2732' Plug bottom w/ 15 sacks cement.

Top of cement 2610' Mud 2610' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 200'

Spotted 35 sacks cement 200' to 100' Mud 100' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2308' of 4 1/2" casing.

~~INVOICED~~

I hereby certify that the above well was plugged as herein stated.

DATE 9-25-73INV. NO. 7987-11Signed: Edgar J. Liles

Well Plugging Supervisor