


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 30 Twp. 23S Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 SE/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Row (Washdown) Well No. 1
Office Address 1432 Wichita Plaza Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 16 19 65
Application for plugging filed November 16 19 65
Application for plugging approved November 16 19 65
Plugging commenced November 16 19 65
Plugging completed November 16 19 65
Reason for abandonment of well or producing formation key-locked



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, 805 Main, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	207	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 200 ft. with 35 sx. cement and 1/2 sk. hulls. Plug and hulls at 35 ft., cement to top

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company
Address 1432 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. J. A. Gilliland (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. A. Gilliland*
1432 Wichita Plaza Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 65

Barbara J. Scott
Barbara J. Scott, Notary Public.

My commission expires December 1, 1968



WELL LOG.

15-145-0357-0000

WELCH & OLSSON DRILLING COMPANY, INC.

ELEVATION: 2075 R.B.

CONTRACTOR: Welch & Olsson Drilling Co. Inc.

Comm. Drlg: 7-15-55

ROW #1

Compl. Drlg: 7-29-55

NW NW SE Sec. 30-23-16W.

Pawnee County, Kansas.

Production: D & A.

Casing Record.

Set 207' of 8 5/8" with 175 sacks of cement.

(Figures indicated bottom of formations.)

<u>FORMATIONS:</u>	<u>DEPTHS</u>		<u>FORMATION TOPS.</u>
Shale:	310	Heebner:	3617 (-1542)
Shale & Red Bed:	550	Brown Lime:	3740 (-1665)
Sand:	615	Lansing--Kansas City:	3747 (-1672)
Red Bed & Shale:	835	Base Kansas City:	4027 (-1952)
Sand & Shale:	1035	Ft. Scott Lime:	4125 (-2050)
Anhydrite:	1080	Cherokee Section:	4156 (-2081)
Red Bed & Shale:	1220	Cherty Conglomerate (Miss.):	4181 (-2106)
Shale:	1270	Viola:	4272 (-2197)
Shale & Shells:	2000	Simpson:	4379 (-2304)
Shale & Lime:	2195	Arbuckle:	4443 (-2368)
Lime & Shale:	2915		
Shale & Lime:	3150		
Lime & Shale:	3600		
Shale & Lime:	3725		
Lime & Shale:	3865		
Lime:	4145		
Lime & Shale:	4180		
Sand:	4185		
Chert:	4271		
Lime:	4375		
Sand:	4448		
Lime:	4480 T.D.		

STATE OF KANSAS,)
) SS:
 SEDGWICK COUNTY,)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the NW NW SE of Section 30, Township 23, Range 16 W. Pawnee County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.
 BY [Signature]
 R. E. WELCH

Subscribed and sworn to before me this 3rd day of August, 1955.

[Signature]
 Notary Public.

My commission expires:
 June 12, 1959

PLUGGING
 WELL SEC 30 T 23 R 16 W
 BOOK PAGE 139 LINE 19