

15-145-00357-0001

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pawnee County, Sec. 30 Twp. 23 Rge. 16 (E) (W)

Location as "NE/CNW&SW" or footage from lines NW NW SE

Lease Owner Welch & Olsson Drilling Co. Inc.

Lease Name Row Well No. 1

Office Address 203 Rule Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 7-29 19 55

Application for plugging filed 7-29 19 55

Application for plugging approved 7-29 19 55


Plugging commenced 7-29 19 55

Plugging completed 7-29 19 55

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 200' and set plug. Cemented and displaced with pump truck. 85 sacks of cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1955 8-19-55

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.
Address 203 Rule Bldg. Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. E. Welch*
203 Rule Bldg. Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 3rd day of August, 1955

My commission expires June 12, 1959

Notary Public.

PLUGGING
FILE SEC 30 T 23 R 16 W
BOOK PAGE 139 LINE 19

15-145-00357-0001

WELL LOG.

WELCH & OLSSON DRILLING COMPANY, INC.

ELEVATION: 2075 R.B.

CONTRACTOR: Welch & Olsson Drilling Co. Inc.

Comm. Drlg: 7-15-55

ROW #1

Compl. Drlg: 7-29-55

NW NW SE Sec. 30-23-16W.

Pawnee County, Kansas.

Production: D & A.

Casing Record.

Set 207' of 8 5/8" with 175 sacks of cement.

(Figures indicated bottom of formations.)

<u>FORMATIONS:</u>	<u>DEPTHS</u>		<u>FORMATION TOPS.</u>	
Shale:	310	Heebner:	3617	(-1542)
Shale & Red Bed:	550	Brown Lime:	3740	(-1665)
Sand:	615	Lansing--Kansas City:	3747	(-1672)
Red Bed & Shale:	835	Base Kansas City:	4027	(-1952)
Sand & Shale:	1035	Ft. Scott Lime:	4125	(-2050)
Anhydrite:	1080	Cherokee Section:	4156	(-2081)
Red Bed & Shale:	1220	Cherty Conglomerate (Miss.):	4181	(-2106)
Shale:	1270	Viola:	4272	(-2197)
Shale & Shells:	2000	Simpson:	4379	(-2304)
Shale & Lime:	2195	Arbuckle:	4443	(-2368)
Lime & Shale:	2915			
Shale & Lime:	3150			
Lime & Shale:	3600			
Shale & Lime:	3725			
Lime & Shale:	3865			
Lime:	4145			
Lime & Shale:	4180			
Sand:	4185			
Chert:	4271			
Lime:	4375			
Sand:	4448			
Lime:	4480 T.D.			

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 19 1955
 CONSERVATION DIVISION
 Wichita, Kansas.

STATE OF KANSAS,)
) SS:
 SEDGWICK COUNTY,)

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the NW NW SE of Section 30, Township 23, Range 16 W. Pawnee County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.

BY R. E. Welch
 R. E. WELCH

Subscribed and sworn to before me this 3rd day of August, 1955.

Scott S. Jones
 Notary Public.

My commission expires:
 June 12, 1959

PLUGGING
 SEC 30 T 23 R 16 W
 PAGE 139 LINE 19